

National Transportation Safety Board Aviation Accident Data Summary

Location: THERIOT, LA Accident Number: FTW99LA179

Date & Time:07/03/1999, 1200 CDTRegistration:N8360TAircraft:Robinson R22 BETAInjuries:2 None

Flight Conducted Under: Part 91: General Aviation - Business

Analysis

The engine of the helicopter lost power during a repositioning flight at 500 feet above ground level. The pilot initiated a straight-in autorotation to a swampy area covered with grass 4 to 5 feet tall. The helicopter settled into the grass, rolled over on its right side and came to rest heading 180 degrees from the direction of the landing. The aircraft was recovered to the helicopter manufacturer's facility for evaluation and repairs. On August 17, 1999, the engine of the helicopter was successfully run for 20 minutes under the supervision of an FAA inspector. The inspector reported that the engine performed within the established parameters. He added that water was drained from the main fuel tank, the gascolator, and the carburetor bowl.

Probable Cause

The National Transportation Safety Board determines the probable cause(s) of this accident to be: The pilot's inadequate preflight inspection which led to a contaminated fuel supply and subsequent loss of engine power. A factor was the lack of suitable terrain available for the forced landing.

Findings

Occurrence #1: LOSS OF ENGINE POWER(TOTAL) - NONMECHANICAL

Phase of Operation: CRUISE

Findings

1. (C) FLUID, FUEL - CONTAMINATION, WATER

2. (C) PREFLIGHT PLANNING/PREPARATION - INADEQUATE - PILOT IN COMMAND

Occurrence #2: FORCED LANDING

Phase of Operation: DESCENT - EMERGENCY

Occurrence #3: ROLL OVER

Phase of Operation: EMERGENCY LANDING

Findings

3. TERRAIN CONDITION - SWAMPY

4. TERRAIN CONDITION - HIGH VEGETATION 5. (F) TERRAIN CONDITION - NONE SUITABLE

Pilot Information

Certificate:Airline Transport; CommercialAge:33Airplane Rating(s):Multi-engine Land; Single-engine LandInstrument Rating(s):AirplaneOther Aircraft Rating(s):HelicopterInstructor Rating(s):NoneFlight Time:8000 hours (Total, all aircraft), 250 hours (Total, this make and model), 7500 hours (Pilot In Command, all aircraft), 120 hours (Last 90 days, all aircraft), 80 hours (Last 30 days, all aircraft), 6 hours (Last 24

hours, all aircraft)

Aircraft and Owner/Operator Information

Aircraft Make: N8360T Robinson Registration: Model/Series: R22 BETA R22 BETA **Engines:** 1 Reciprocating ROBERT J. NEIDER **Engine Manufacturer:** Operator: Lycoming Operating Certificate(s) **Engine Model/Series:** O-360-J2A None Held: Flight Conducted Under: Part 91: General Aviation - Business

Meteorological Information and Flight Plan

Conditions at Accident Site:	Visual Conditions	Condition of Light:	Day
Observation Facility, Elevation:	, 0 ft msl	Weather Information Source:	Pilot
Lowest Ceiling:	None / 0 ft agl	Wind Speed/Gusts, Direction:	10 knots / , 180 $^{\circ}$
Temperature:	32°C	Visibility	10 Miles
Precipitation and Obscuration:			
Departure Point:		Destination:	

Wreckage and Impact Information

Crew Injuries:	1 None	Aircraft Damage: Substantial
Passenger Injuries:	1 None	Aircraft Fire: None
Ground Injuries:	N/A	Aircraft Explosion: None
Latitude, Longitude:		

Administrative Information

Investigator In Charge (IIC):	HECTOR	r Casanova	Adopted Date:	09/12/2000
Investigation Docket:	Dockets re at pubing	eleased prior to Jun	ne 1, 2009 are publicly availabl 0-877-6799. Dockets released	chival information for the NTSB's investigations. e from the NTSB's Record Management Division after this date are available at

The National Transportation Safety Board (NTSB), established in 1967, is an independent federal agency mandated by Congress through the Independent Safety Board Act of 1974 to investigate transportation accidents, determine the probable causes of the accidents, issue safety recommendations, study transportation safety issues, and evaluate the safety effectiveness of government agencies involved in transportation. The NTSB makes public its actions and decisions through accident reports, safety studies, special investigation reports, safety recommendations, and statistical reviews.

Page 2 of 3 FTW99LA179

